


# pool collection





**We form  
partnerships  
as reliable as  
our pools**

Austria  
Belgium  
Croatia  
Czech republic  
Denmark  
Estonia  
Finland  
France  
Germany  
Greece  
Hungary  
Israel  
Italy  
Latvia  
Litauen  
Luxembourg  
Montenegro  
Netherlands  
Norway  
Poland  
Romania  
Serbia  
Slovakia  
Slovenia  
Spain  
Sweden  
Switzerland  
Ukraine  
United Kingdom  
Turkey



**30 countries  
110+ Compass Partners**



82,000+ COMPASS POOLS SOLD IN AUSTRALIA AND EUROPE - THANK YOU - EVERY SINGLE POOL COUNTS!

# compass timeline



**2005**


Foundation of the COMPASS Europe plant with the technologies of the Australian production process **Delivery of the first COMPASS pools to Europe**

**2008**

Foundation of COMPASS Pools Germany with own central warehouse in Lower Bavaria

**2008**

Compass pool cover **introduced!** – unique roll-up covers that have been exclusively developed for Compass Europe



**2012**


Compass Europe established among leading pool manufacturers in Europe

**2014**

**EXCELLENCE IN DESIGN** After the introduction of the Yacht Pool to the market we won the Reddot – Award as well as the iF-Design Award



reddot award




**2016**

**Opening ceremony of the New COMPASS Europe factory:** In one year we rebuilt, furnished and opened the new production. We became the most modern and environmentally friendly pool manufacturer in the EU

**2018**

New innovations with the **High-level skimmer** and the new model **Trend 73**



**2020**

Compass celebrates the most successful year in the company's history

**2022**

**Fresh wind & continuity – Change of ownership at Compass Europe – Franz Reps & Tibor Meszaros.**

**8 new pool models introduced**



**1980**

**Australia** Foundation of the COMPASS parent plant in Australia



**2007**

Development of the **Cyber colors** and new pool shape with Roman stairs and straight pool bottom

**2010**

Opening of the COMPASS Pools – showroom in Munich



**2013**

**COMPASS carbon – revolution:** Adding carbon to our pools gave our product even more stability and durability

**2015**

**Fire in COMPASS – Factory:** One of the hardest times for COMPASS Europe was in the summer of 2015 when the production hall burned down



**2017**

We developed three **new pool models** and launched the Aqua Nova and XL-Lounger line

**2019**

We develop the first Infinity pool from COMPASS Pools



**2021**

COMPASS Europe – Hosted Europe's largest pool conference in Europe in Dubai







# Our belief

We are proud to be a long-standing pool manufacturer with Australian roots backed by over 40 years of manufacturing expertise, during which time Compass Pools has built up an excellent international reputation.

With the perfect combination of quality, design and innovation, we are able to consistently produce a premium class product. Our pools are hand finished with the utmost care and unique carbon-ceramic technology.

Driven by our passion for pools, our desire is to offer our clients fascinating moments of relaxation and well-being of the highest quality.

Your perfect pool is what drives us.



**Franz Reps**  
CEO Compass Europe



**Tibor Mészáros**  
COO Compass Europe



# Inspired by story

**Your pool – Let your dream become reality and plunge yourself into an unforgettable experience. With an original COMPASS CARBON CERAMIC POOL you will experience incomparable hours at home.**

Since the founding of the Compass Europe factory, more and more pool lovers around the world have been enjoying a pool experience in a class of its own. The improvement in the quality of life of every single pool owner and the thrilled sparkle in the eyes of our customers prove that we are doing the right thing day after day!

XL-Trainer 110 FB | Nova Grey  
Compass Pools UK



1980-2022 82,000+ POOLS SOLD WORLDWIDE – COMPASS POOLS SUCCESS STORY





**Happiness is only  
real when shared**





 pool  
collection



← Compass Pools Gallery

XL Trainer 110 | Nova Grey | Compass Pools UK



# new new Poolseries classic




Classic 103




Classic 93



Classic 83



Classic 73



Classic 63



Classic 53

Type	Length	Width	Depth	Capacity	Weight
Classic 53	5,30 m	3,15 m	1,50 m	16 m <sup>3</sup>	600 kg
Classic 63	6,37 m	3,15 m	1,50 m	20 m <sup>3</sup>	700 kg
Classic 73	7,37 m	3,15 m	1,50 m	23 m <sup>3</sup>	850 kg
Classic 83	8,37 m	3,52 m	1,50 m	31 m <sup>3</sup>	950 kg
Classic 93	9,37 m	3,52 m	1,50 m	35 m <sup>3</sup>	1200 kg
Classic 103	10,37 m	3,52 m	1,50 m	39 m <sup>3</sup>	1300 kg







# garden plunge pools


## Smaller than 6.50 m

These pools are ideal for a lot of fun in a small space. You can choose from a range of models perfectly designed for smaller gardens due to their compact design and size. Equipped with a counter-current system, they can also please the sporty type.



≤10 m<sup>2</sup>  
water surface

# new



CompassSwim 50



CompassSwim 60

## CompassSwim – the all-rounder among the Compass pools.

Regardless of whether it is installed in-ground in the garden or above-ground and installed as a self-supporting pool on the terrace. CompassSwim is suitable for both types of installation. With its compact sizes, there is room for the CompassSwim on many terraces. Equipped with massage jets and a turbine system, the CompassSwim can be used as a whirlpool and swimming pool in one.

Build your private **passive pool**. In combination with an energy-saving pump and photovoltaic system, the CompassSwim can be used as a passive pool. You can decide independently whether your passive pool is operated with a sand or cartridge filter.

CompassSwim can do both.

Type	Length	Width	Depth	Capacity	Weight
CompassSwim 50	5,00 m	2,45 m	1,35 m	10 m <sup>3</sup>	600 kg
CompassSwim 60	6,00 m	2,45 m	1,35 m	12 m <sup>3</sup>	700 kg

Classic 62 | Nova Grey | Compass Pools Netherland




Fun 74 | Nova Navy  
Reps Pools


Baby Pool | Nova Navy | Compass Pools Israel



# small garden pools




### Brilliant 66 / 74



Steps with anti-slip surface  
Relaxzone and Massage nozzles optional

### Classic




Relaxzone and Massage nozzles optional

Optional space for the Rollo Cover

Integrated rail for the safe guidance of Rollo cover

### Aqua Nova 53




Optional space for the Rollo Cover

Relaxzone and Massage nozzles optional

Integrated rail for the safe guidance of Rollo cover

### XL-Trainer 72




Relaxzone and Massage nozzles optional

Integrated rail for the safe guidance of Rollo cover

Space for Rollo cover or massage nozzles

### Trend 73



Integrated technical shaft (optional) with cover in pool colour to fit the filter system

Relax zone and massage jets option


Integrated high-level skimmer for the maximum height of water level

Steps with anti-slip surface

Optional space for the Rollo Cover

Integrated rail for the safe guidance of Rollo cover

### Fun 74 Fun 74 S



Relaxzone and Massage nozzles optional


Optional space for the Rollo Cover

Steps with anti-slip surface

Safety steps and handrail, if applicable

\*S without safety step

### X-Trainer 45




Relaxzone

Steps with anti-slip surface

Deeper side

Relaxzone and Massage nozzles optional


### Baby-Pool



Relaxzone and Massage nozzles optional

Optional Space for the Rollo Cover

### Classic Top




Integrated rail for the safe guidance of Rollo cover

Relaxzone and Massage nozzles optional

Optional space for the Rollo Cover

Type	Length	Width	Depth	Capacity	Weight
X-Trainer 45	4,45 m	2,94 m	1,21-1,49 m	15 m <sup>3</sup>	600 kg
Aqua Nova 53	5,30 m	3,20 m	1,50 m	21 m <sup>3</sup>	700 kg
Classic	6,16 m	3,16 m	1,50 m	23 m <sup>3</sup>	700 kg
Classic Top	6,37 m	3,23 m	1,10 m	20 m <sup>3</sup>	500 kg
Baby-Pool	6,52 m	2,40 m	0,88 m	12 m <sup>3</sup>	600 kg
Brilliant 66	6,62 m	3,62 m	1,40 m	27 m <sup>3</sup>	850 kg

### Riverina 67



Integrated handrail and a safety step along the pool

Steps with anti-slip surface

Relaxzone and Massage nozzles optional

Deeper side

Relaxzone

Type	Length	Width	Depth	Capacity	Weight
Riverina 67	6,72 m	3,44 m	1,11-1,57 m	24 m <sup>3</sup>	800 kg
XL-Trainer 72	7,19 m	3,30 m	1,50 m	30 m <sup>3</sup>	920 kg
Trend 73	7,30 m	3,30 m	1,50 m	31 m <sup>3</sup>	1100 kg
Fun 74	7,48 m	3,68 m	1,50 m	35 m <sup>3</sup>	1050 kg
Fun 74 S	7,50 m	3,71 m	1,50 m	35 m <sup>3</sup>	1050 kg
Brilliant 74	7,63 m	3,64 m	1,40 m	32 m <sup>3</sup>	920 kg






# medium pools

7.70 – 9.00 m

Our most sought-after pools are ready to shine like a diamond in any garden or home. Simply add a few water features and let the family have real fun.






XL-Lounger 115 | Nova Anthracite  
Hügel mehr Garten




# Infinity High-End -Pool



Infinity 80 | Nova Stone  
Reps Pools

# infinity

## Infinity 80



### Pool with boundless water surface

#### Perspective over the horizon

Incomparable attractiveness and spectacular views are achieved by the boundless fusion of the water surface with the surroundings.

Tile overflow channel creates a unique water-stone look that can be discreetly yet elegantly integrated into the garden setting, creating a harmonious whole.

Optionally, the infinity pool can also be installed with a grating instead of a stone channel.

more →



Type	Length	Width	Depth	Capacity	Weight
Infinity 80	8,30 m	4,05 m	1,46 m	40 m <sup>3</sup>	1100 kg

Infinity 80 | Nova Stone | Reps Pools



# new





# medium




XL-Trainer 110 | Nova Navy  
Compass Pools UK


Fun 80  
Fun 80 S\*  
Fun 80 D\*\*




X-Trainer 82



XL-Briliant 88



Aqua Nova 77  
Aqua Nova 84



Type	Length	Width	Depth	Capacity	Weight
Aqua Nova 77	7,75 m	3,55 m	1,50 m	36 m <sup>3</sup>	1000 kg
Aqua Nova 84	8,40 m	3,55 m	1,50 m	42 m <sup>3</sup>	1200 kg
Fun 80	8,00 m	3,70 m	1,50 m	38 m <sup>3</sup>	1100 kg
Fun 80 S	8,00 m	3,70 m	1,50 m	38 m <sup>3</sup>	1100 kg
Fun 80 D	8,00 m	3,70 m	1,50 m	38 m <sup>3</sup>	1100 kg

\*S without safety step

\*\*D deeper BeachLine cover and high-level skimmer for an even better pool experience



Fun 80 | Nova Anthracite | Compass Pools Israel

Type	Length	Width	Depth	Capacity	Weight
X-Trainer 82	8,25 m	3,68 m	1,09-1,76 m	36 m <sup>3</sup>	960 kg
XL-Briliant 88	8,70 m	3,75 m	1,50 m	45 m <sup>3</sup>	1100 kg







# large pools

9.00 – 13.30 m


It doesn't matter whether you are looking for a pool for amusement and relaxation or for sporting activities. The Premium Family Large Pools from Compass Pools can do both.





**enjoy  
well deserved  
respite actively**





# large pools

XL Trainer 110 | Nova Anthracite  
Compass Pools Netherland



XL-Fast Lane 122 | Nova Navy | Reps Pools




XL-Trainer 110 FB | Nova Grey | Compass Pools UK





# Large

## Riverina 106



Integrated handrail and a safety step along the pool

## Fun 100




Steps with anti-slip surface


Integrated rail for the safe guidance of Rollo cover



## Java 101



## XL-Java 114




Integrated rail for the safe guidance of Rollo cover

Space for Rollo cover or massage nozzles

Video →




## XL-Lounger 95 / 115



Optional space for the Rollo Cover

Relaxzone and Massage nozzles optional

## XL-Trainer 110 FB\*




Space for Rollo cover or massage nozzles

\*FB - Flat Bottom

Type	Length	Width	Depth	Capacity	Weight
XL-Lounger 95	9,52 m	4,06 m	1,50 m	50 m <sup>3</sup>	1200 kg
XL-Trainer 110 FB	11,02 m	4,02 m	1,50 m	52 m <sup>3</sup>	1350 kg
XL-Lounger 115	11,50 m	4,06 m	1,50 m	59 m <sup>3</sup>	1450 kg




XL-Java 114 | Golden Pebble | Compass Ukraine



Type	Length	Width	Depth	Capacity	Weight
Fun 100	10,00 m	4,00 m	1,50 m	52 m <sup>3</sup>	1300 kg
Java 101	10,03 m	3,80 m	1,50 m	49 m <sup>3</sup>	1200 kg
Riverina 106	10,62 m	3,78 m	1,04-1,88 m	45 m <sup>3</sup>	1400 kg
XL-Java 114	11,40 m	3,96 m	1,10-1,68 m	52 m <sup>3</sup>	1350 kg






Video →




**yacht pool**  
Awarded with two design awards




Yacht Pool | Compass Pools Israel

### Yacht Pool




- integrated SPA for 2 persons (with 33 massage nozzles)
- genuine yacht flex-teak floor
- stainless steel handrails
- position lights (L and R)



**XL-Fast Lane 122**  
Nova Anthracite | Reps Pools



### XL-Fast Lane 122



### XXL-Trainer 133



**XL Lounger 115** | Nova Anthracite  
Netherland

Type	Length	Width	Depth	Capacity	Weight
Yacht Pool	11,54 m	4,04 m	1,50 m	42 m <sup>3</sup>	1200 kg
XL-Fast Lane 122	12,15 m	2,89 m	1,50 m	43 m <sup>3</sup>	1500 kg
XXL-Trainer 133	13,28 m	4,49 m	1,50 m	75 m <sup>3</sup>	2400 kg





# Colour your Pool

Brilliant 74 | Nova Grey | Belgium

# COLOUR

## essence that sets apart

Compass Pools' arguably most distinctive feature, and the attribute that sets us apart from our competitors, is the breathtaking use of colour and the high-gloss & high-quality finish. Compass has the colours to match your happiest holiday memories. Design your own sea in your garden!

### Nova® Colours

The Nova® range is one of the most advanced systems in the world, utilising new types of colour 'chips' and base colour blends. Its translucent holographic effect give all Nova® colours a distinctive brilliance.

#### Characteristics

- 2 special layers of paint applied independently on the surface
- produces deep, lustrous colour effects akin to the most beautiful marine lagoons
- the layers of paint are applied by hand like the most prestige cars - that's why each pool is an original
- using the latest technology of Nova™ paint layer

### Bi-Luminite®

The Bi-Luminite® surface and its '3D' colours are a true revolution in pool finishes, and yet another feature unique to Compass Pools. These colours change the look of composite pools thanks to tiny glittering particles just below the top-coat and the application of two paint layers as opposed to just one. The patented Bi-Luminite® process creates unique colour effects not found in any other pool finish.



# Nova<sup>®</sup> colours




Nova<sup>®</sup> Stone | Réunion Island



Nova<sup>®</sup> Anthracite | Seychelles



Nova<sup>®</sup> Pearl | Zanzibar



Nova<sup>®</sup> Grey | Croatia



Nova<sup>®</sup> Navy | Maldives



Nova<sup>®</sup> Blue | Madagascar

# Bi-Luminate<sup>®</sup>



Bi-Luminate<sup>®</sup> Golden Pebble | Tahiti



Bi-Luminate<sup>®</sup> Blue Granite | Bora Bora




Bi-Luminate<sup>®</sup> Smokey Quartz | Mauritius



Bi-Luminate<sup>®</sup> Blue Sapphire | Hawaii



Cyber White | Thailand



Papyrus White | Greece





Fun 80 | Nova Stone | GARTEN HANDWERK – BÖSCH



Fun 74 | Nova Navy | Bazeni Ema





# innovation & technology



easy & quick installation



Carbon Ceramic Technology





40-year factory guarantee on tightness



Vantage self-cleaning system



Salt-friendly

- Carbon Ceramic layer  
- Improved formula for even greater stability and durability 
- High-Level-Skimmer
- HydroProtection 
- constant development of new and modern negative moulds
- Vantage – Self-Cleaning Pool
- Nova® colours

## Compass Pools pioneering the world's cutting-edge Ceramic Technology

In the mid 90's, when Compass Pools introduced ceramic technology to the pool industry, it quickly became the recognised technology around the world. For decades, we have been recognised as a world leader and innovator in the market.

### Advantages

- exclusive, radiant three-dimensional shine without surface cavities
- 40-year factory guarantee on the tightness of the pool and against osmosis.
- ceramic core (patent PN 1690), increased strength without loss of elasticity
- quick and easy installation of the pool in a few days
- installation possible without concrete base plate
- high quality due to constant monitoring of the strict, compliance-verified technology of the Australian production process
- absolutely temperature resistant
- suitable for salt water operation
- energy-saving features – superior thermal insulation properties



# factory



#### Factory innovations since 2016

- Modern spray devices and negative moulds
- Patented air exchange technology
- Significant reduction of emissions
- Flexible in daily production
- TOP quality emission control
- 40-year factory guarantee on pool tightness and against osmosis

## Compass Factory

#### Our promise

The secret to the success and longevity of our Compass Carbon Ceramic Pools lies in its patented ceramic core.


When you choose an original COMPASS finished swimming pool, we promise you a product of the highest level and exceptional quality. Since 2005, we have been producing more than 1,500 original Compass Ceramic Pools per year in our European factory.

The secret of our success certainly lies in our patented ceramic core and a number of innovations, such as the addition of carbon to our proven multi-layer wall construction.

find out more →




44 pool collections



„Your Perfect Pool is what drives us!“

Compass Europe






SUPER-TOUGH POOL YOU CAN RELY ON!




XL-Trainer 110 | Nova Navy | Compass Pools France



# carbon ceramic pools®

### Features

- even more strength (20%)
- even higher stability
- even better manipulation



latest technology of the Nova™ colour coating



additional rigidity

Vinylester Base coat

Glasfibre-reinforced vinyl ester layer

Glass fibre compound

Ceramic layer



CARBON Edition®

exterior top coat

Glass fiber layer

The additional use of carbon in the patented Ceramic System reinforces the structurally highly stressed areas of the pool.

Carbon has the highest pressure resistance of all reinforcing materials. The same high strength material found in automotive, marine and aerospace components is used for the our pools.



# carbon

### Standard Fiberglass



latest technology of Nova™ – colour layer

Vinylester undercoat

Glass fibre reinforced vinylester layer


Ceramic layer

Reinforced carbon layer

Glass-fibre reinforced polyester layer

Insulating coating, water-resistant

### Carbon Ceramic Pools – exklusiv made by Compass





# new hydropro system

## Introducing our exclusive hydropro system

Compass Pools can now offer you even better protection with our exclusive hydrostatic warranty. One of the potential risks of owning any swimming pool is the possibility of damage due to a hydrostatic event. Essentially, 'hydrostatic damage' can occur when the water level in the ground rises higher than the water level in your pool. When this happens, your pool will naturally want to lift or float... a bit like a boat. As the ground water subsides again, and the pressure on your pool reduces, it can result in permanent bulges or cracks in the walls and floor.

## Our revolutionary new protection system

Our new patented and exclusive hydrostatic valve system has been developed to dramatically reduce rising ground water pressure at rates that are 5 times greater than industry standard valves used in fibreglass pools. In what we believe is a world first, we are now able to offer a lifetime warranty against damage caused by hydrostatic pressure – which is nearly always excluded from home insurance policies and manufacturer's warranties. The HydroPro™ valve can be ordered as an option on any model from February 2023.

## Protection from extreme weather events

With the increasing regularity of extreme weather events and unprecedented rainfall, we wanted to eliminate this risk for all Compass Pools customers. The key to stopping any damage from occurring is to be able to quickly release growing ground water pressure before it's too late. The Compass Research and Development team have spent the last three years testing and perfecting a patented hydrostatic valve that is so sensitive and has such high flow rates that we can now offer a unique hydrostatic damage warranty.








XL-Lounger 115 | Nova Anthracite | Hügel mehr Garten

Brilliant 74 | Nova Grey | Compass Pool Belgium



50 pool collections



XL-Trainer 110 | Nova Grey | Compass Pools UK




A woman with her hair in a bun is relaxing in a swimming pool. She is leaning against the edge of the pool, with a rolled-up white towel and two yellow flowers behind her head. Her eyes are closed, and she has a peaceful expression. The background shows a stone wall and some greenery.

 **the art of  
doing nothing**



# vantage

- Key advantages**
- self-cleaning of the pool up to 80 %-90 %
  - better water circulation & pool hydraulics
  - less disinfectant required
  - no more manual cleaning (e.g. filter bag) required
  - more time to relax and unwind



## self-cleaning pool

scan for more info →



**Imagine a pool that cleans itself, saves money and uses fewer chemicals.**

A spring in the mountains is a symbol of purity and freshness. What is the reason for this? It is in constant motion. The mountain stream takes dirt and dust with it. Since the water circulates, algae and bacteria have no chance to grow. Of course you can achieve the same effect in your pool – through the Vantage self-cleaning system!

VANTAGE is the world's best circulation and cleaning system and is unsurpassed as a pool cleaner. The Vantage system cleans more effectively and more efficiently

from the surface to the bottom of the pool. The Vantage system is almost invisible and does not affect the appearance of your new and beautiful swimming pool. The Vantage system comes in three different nozzle and bracket colours to match your pool colour.

If you want to relax next to your new pool, choose the Vantage system!





# Rollo Cover Beach Line



**The Compass Pools Rollo Cover, an integrated slat cover, guarantees you maximum energy efficiency and absolute safety around your pool.**

The Compass Pools Rollo Cover „Beach Line“ is a special construction made of V4A stainless steel for an integrated underwater bench. Thanks to the high-level skimmers laminated into the pool, a significantly higher water level, almost to the edge of the pool, is achievable. The slats are rolled up below the water level and separated from the swimming area with a pool-coloured separation wall. The top of the construction can be covered with a tile stone or with a pool-coloured cover.

The Compass Pools Rollo Cover can withstand the weight of a pet, a child and even an adult – up to a maximum of 100 kg – water level in the pool must be correct and the cover is fully extended. For child safety in accordance with the French standard NF P 90-308, an additional safety fastening is required on the pool opposite the roller shutter shaft.

An integrated support edge in the pool prevents the roller slats from sinking and an additional safety fastening on the opposite side of the roller shutter shaft fulfils the requirements of the French standard. The Compass Pools Rollo Cover Solar slats are made of hard

PVC (polycarbonate or anti-algae slats optional) with improved resistance to mechanical damage and UV radiation.

scan to find out more →



**The latest generation of polycarbonate lamellas are manufactured using the Quadro extrusion process. This technology is unique in the world of swimming pool covers. It enables T&A to produce a perfect solar lamella that is extremely shock resistant and durable and combines solar, anti-algae and anti-condensation effects. The slats are available in the Quadro Black Edition and Quadro Titanium Edition variants.**





# slatted


Colour finishing




PVC White ↑



PVC Sand ↑



PVC Blue ↑



PVC Grey ↑



Quadro Black ↑

new



PVC Solar ↑



PVC Transparent ↑



Polycarbonate Solar ↑




Polycarbonate Transparent ↑



Quadro Titanium ↑

new



Polycarbonate Solar Anti Alge ↑



Polycarbonate ALU Anti Alge ↑




Polycarbonate ALU Look ↑



## Compass Rollo Cover Benefits

- Guarantees maximum energy efficiency and full safety
- solar lamellas provide optimum heating of the swimming pool water of an additional 4°-8°C
- during the night, evaporation and thus heat loss are reduced to a minimum
- uniquely high water level - thanks to laminated high-level skimmers

## Detail beachline:




# rollo cover




# models


Rollo cover beachline compatible with the following models



XL-Lounger 95 / 115



XL-Trainer 110 FB



XXL-Trainer 133




Trend 73



Classic 53



Classic 93




XL-Java 114




XL-Briliant 88



XL-Fast Lane 122




Classic




Classic 63




Classic 103




Fun 74




Fun 80




Infinity 80




Fun 100




Classic 73




XL-Trainer 72




Yacht Pool




Aqua Nova 53




Aqua Nova 77



Aqua Nova 84



Classic 83





# Overground

## AquaTop – the standard above-ground variant

The roll-up mechanism of this model is made of stainless steel AISI 316L. A 24 V electric motor is mounted in one of the two consoles. The control and the key switch are integrated separately in the pool technology. This means that the roll-up device can be completely covered.



## Top Moov – the mobile cover with style

It is always a challenge to find a cover for an existing pool while retaining the design and character of the pool installation. TopMoov is the optimal solution for this. It looks elegant and can be moved a few metres with discreet rails. TopMoov is always equipped with solar drive.



# Rollo cover overground

The above-ground roller shutter cover promises the highest quality and durability.

The slatted covers can be used for newly installed pools as well as for existing pools.


A roll-up mechanism at the end of the pool automatically winds and unwinds the blades. For the overall appearance, the roll-up device can be coated with wood or matched to the garden and pool design.

## EcoTop Plus – the classic and exclusive above-ground variant

The simple and exclusive solution for maximum comfort

### Advantages

- Winding shaft made of GRP
- Powder-coated stainless steel supports – optionally white or anthracite grey – in combination with high-quality IPE wood
- Motor with transformer and control or solar drive with key switch and remote control
- Optional, on-site cladding with wood (not with solar panel)



# Safety Compass Cover

The Compass COVER safety cover makes your pool safe for children. Sturdy, anodised aluminium profiles, cover elements made of reinforced, elastic PVC with an anti-abrasive top surface and a secure fastening system guarantee absolute safety around your pool.



### Main advantages

- Absolute safety for children and pets
- According to the French safety standard
- High quality, antibacterial polyester fabric, PVC coated
- UV resistant
- Temperature resistant from -30° to +70°C
- All-round high-frequency welded edge (25 mm)
- Rain drainage holes between the support profiles
- Support profiles made of anodised aluminium
- Exchangeable profiles and cover elements
- Simple and secure fastening system







**Key advantages**

- Aluminium frame profiles in various standard and effect colours
- "Floating" installation of the glazing
- Super-flat guide rails
- Special guide rails with maintenance-free stainless steel ball bearings
- Permanent protection against dirt and wind

QUALITY, MADE TO MEASURE ENCLOSURE SOLUTION

# Pool enclosure

CompassPools roof are enclosures with colours and dimensions adapted to Compass pools. CompassPools roof uses the best results achieved in this field, inclusive of our multiple patents.



**Key advantages**

- Maintenance-free brushless DC motor
- Maintenance-free sliding bearing
- Motor controller with current and temperature monitor
- No manhole or pipework necessary
- All components are made of 316Ti, 316L or high-quality plastic
- Control via radio remote BINDER-Control and optionally via a piezo switch
- Easily create training programs with the optional app
- Optional brine water resistant version
- Maintenance-free operation



# hydrostar turbine system



Turbines generate a wide, even and powerful flow. It is up to you to set the strength of the flow!

Energise yourself while the current carries you – Wellness for your soul.

The Hydrostar turbine system brings the natural feeling of swimming into your home. With individually adjustable speed – for all needs.



One for all. Hydrostar!

Patented technology makes this possible: turbines generate a broad, even and powerful current. You decide how strong it should be. HydroStar is easy to install and can also be fitted retrospectively with the help of the Easystar.





Aqua Nova 77 | Nova Pearl | Reps Pools



Fun 74 | Nova Pearl | Compass Pools Hungary



FUN 100 | Nova Pearl | Reps Pools





- Advantages for your pool**
- asy cleaning / maintenance
  - automatic and manual tank venting included
  - inner piping made of corrosion-resistant plastics
  - includes filter star, pressure gauge and tank drainage
  - no (expensive) cartridges / filter media
  - No sand undercutting
  - Market-proven filter technology

# sand filter tanks and pumps

The latest generation of filter tanks with large opening at the top and wide outlet. The filter tanks are made of high quality glass fibre reinforced plastic.



## Pumps – Compass Pump and Compass Pump Pro

- Benefits for your pool**
- Minimal energy consumption
  - Self-priming pump
  - Made of fiberglass-reinforced material for a very wide range of applications
  - Very quiet running
  - Up to 5 years manufacturer's warranty (depending on model).



**Compass Pump**  
Proven endurance runner with high flexibility and performance



**Compass Pump Pro**  
Established and reliable – Premium water circulation pump with 5-year quality guarantee





**Compass Pump VS**  
Intelligent, fast and quiet – highly efficient circulating pump that makes full use of its performance



**Compass Pump Pro VS**  
Premium-efficient & super-quiet Intelligent circulation pump for more demanding users


## Embedded High-Level-Skimmer

The high-level skimmer (surface suction) integrated into the pool wall enables a very high water level just below the pool edge – close to Infinity design. The high water level ensures an exclusive and elegant appearance of the swimming pool installation. The skimmer is integrated in the production process, so no separate flanges and cut-outs in the pool wall are necessary and the stability of the pool is not affected in any way.



## Colour matched outlet

Special barrier-free swimming pool floor drain in the colour of the pool – no elevation (no flange – but firmly laminated) in the pool area! In addition, we offer the complete accessories such as a counter-current system, spotlights, stainless steel trim, and a level adjustment.





# pool heat pumps

## Pool heat pump – Compass pools inverter PPIC



The latest generation of inverter heat pumps. The patented InverPad Turbo fan motor system optimises the most advanced technology in noise.

Air source heat pumps with InverPad Turbo technology are suitable for operation in colder weather. Thanks to the airflow of the InverPad Turbo, the heating capacity of the air source heat pump is maximised to ensure excellent performance even in cold conditions. Enjoy your pool – in all four seasons

### Advantages of Compass Pools Inverter PPIC:

- 10 times quieter than conventional inverter units
- Mitsubishi compressor
- Wifi as option
- modern control
- perfect performance
- trendy design

### Technical Information

	PPIC 11	PPIC 14	PPIC 17	PPIC 22	PPIC 27	PPIC 32S	PPIC 41S
<b>Operating conditions: Air 27°C / Water 27°C / Humidity 80 %</b>							
Heating capacity (kW) PERFECT MODE	8,8	10,4	13	17,5	20,3	26,8	34,5
COP – scale	15,0–7,3	15,0–7,4	15,0–7,1	15,5–7,4	15,2–7,3	15,8–7,2	16,0–7,0
Heating capacity (kW) POWER MODE	11	13,8	17	22	26,5	31,5	40,5
<b>Operating conditions: Air 15°C / Water 26°C / Humidity 70 %</b>							
Heating capacity (kW) PERFECT MODE	5,8	7,6	9,2	12,4	14,4	18	23,9
COP – scale	7,5–5,0	7,6–5,1	7,8–5,0	8,2–5,1	7,9–5,2	8,0–5,0	8,3–5,1
Heating capacity (kW) POWER MODE	7,3	9,2	11,5	15	18	22,1	29
<b>Technische Spezifikation</b>							
Recommended pool volume (m³)	20–45	30–55	35–65	40–80	50–95	60–120	85–160
Operating ambient air temperature (°C)	-15°C ~ 43°C						
Power supply	230 V						
Compressor type	Twin – Rotary DC compressor						
Noise level at 1 m dB (A)	36,3 ~ 44,5	36,5 ~ 45,9	39,3 ~ 46,7	39,5 ~ 49,8	39,8 ~ 50,2	40,5 ~ 50,9	40,6 ~ 51,3
Noise level at 50 % dB (A)	38,4	40,3	42,2	43,1	43,0	45,6	45,7
Noise level at 10 m dB (A)	16,3 ~ 24,5	16,5 ~ 25,9	19,3 ~ 26,7	19,5 ~ 29,8	19,8 ~ 30,2	20,5 ~ 30,9	20,6 ~ 31,3
Rated input power (kW)	0,21 ~ 1,55	0,25 ~ 1,92	0,31 ~ 2,44	0,40 ~ 3,05	0,49 ~ 3,80	0,60 ~ 4,70	0,79 ~ 6,10
Rated input current (A)	0,91 ~ 6,74	1,09 ~ 8,34	1,35 ~ 10,60	1,74 ~ 13,26	2,13 ~ 16,52	0,86 ~ 6,81	1,14 ~ 8,84
Noise level at 10 m dB (A)	16,3 ~ 24,5	16,5 ~ 25,9	19,3 ~ 26,7	19,5 ~ 29,8	19,8 ~ 30,2	20,5 ~ 30,9	19,6 ~ 31,3
Dimensions (LxWxH)	770x 530x 656	770x530x 656	770x 530x 656	1007x530x756	1162x536x756	on request	on request



# pool heat pumps

## Technical information

Model		PHP030E-K	PHP040E-K
max. heating capacity	KW	13,8	18,2
	BTU/h	47000	62000
max. cooling capacity	KW	N/A	N/A
	BTU/h	N/A	N/A
Power consumption (H/K)	KW	2,1	3,0
Power consumption (H/K)	Ampere	10,4	6,1
Power supply	V/Hz	220-240/50	380-400/50
Compressor type		Rotary	Rotary
Noise level	dbA	54	56
Water connection	mm	32	50
min. Water flow	m <sup>3</sup> /h	4,5	6,0
Dimensions (LxWxH)	mm	956/385/600	1115/455/868
Transport dimensions	mm	1040/415/615	1220/510/880
Weight/transport weight	kg	55/64	83/97

## Advantages for your pool

- Corrosion resistant Titanium PVC heat exchanger (5 years warranty)
- Also available as inverter heat pump
- 100 % suitable for saltwater or any other type of water treatment
- Standard integrated automatic defrost with programmable parameters
- Quiet operation
- Eligible for outdoor installation
- Solid and corrosion
- proof finish ensures years of reliable operation
- Plastic housing
- Easy installation
- Reduction of pollutant and CO<sub>2</sub> emissions
- Cost-effective energy
- Prolongation of the swimming season



## Special advantages of the inverter air heat pump

- Continuously variable power control
- Always works at the optimum operating point
- Lower power consumption
- Modern design
- Longer service life
- Quieter than conventional heat pumps

## Technische Informationen

Model		PHP030-IV
max. heating capacity	KW	2,85-12,0
	BTU/h	40800
Power consumption (H/K)	KW	0,21-2,12
Power supply	V	220-240 V
Compressor type		Rotary
Noise level	dbA	22-32
Water connection	mm	50
min. Water flow	m <sup>3</sup> /h	4,2
Dimensions (LxWxH)	mm	950x400x620
Underlying conditions		Outdoor temperature 24°C / Water temperature 26°C

# Air heat pump






Classic | Nova Stone | Compass Pools Ukraine



XL-Lounger 95 | Papyrus White  
Vita Bad AG



XL-Trainer 110 | Nova Navy | Compass Pools UK



# Swimming pool

## Robotic Pool Cleaner



S200

- for pool lengths up to 10 m
- cleans the pool floor and walls



S300i

- for swimming pool lengths up to 15 m
- cleans the entire swimming pool with pool bottom, pool walls and waterline

## water disinfection

### Salt Water Station

**des-OL Hydrolysis systems represent a new concept for disinfecting your pool. They improve water quality without the use of chemical products and greatly simplify maintenance.**

In minimally salty water (between 1 and 2 g of salt per litre), sodium hypochlorite (liquid chlorine, ozone and oxygen) is continuously and automatically produced to disinfect the water. This substitutes 100 % of the added chlorine, eliminates harmful chloramines and results

in completely odourless water. The hydrolysis systems produce chlorine as well as ozone and oxygen.


The salt required for this must be added to the pool water in a concentration of 1 – 2 kg/m<sup>3</sup> (15 times less than is present in seawater). Water treatment with hydrolysis is a self-contained system in which no salt is consumed. The chlorine generated, together with ozone and oxygen, destroys organic matter and pathogens present in the water before it is converted back into sodium chloride (common salt). The chlorine is formed as a fission product of hydrolysis, acts and then decomposes

back to salt. This explains why the salt concentration in the water remains constant and why its consumption does not increase.

The chlorine, ozone and oxygen produced by salt water hydrolysis are not harmful to bathers. It does not irritate the eyes or skin and ensures complete bathing enjoyment. In addition, salt water hydrolysis produces more pleasant and softer water than other disinfection methods. The process completely replaces the purchase, handling and storage of chemical products. It is also suitable for people with chlorine allergies and skin problems.

# water treatment

### Benefits for your swimming pool



- A** Precise brushing and maximum cleaning efficiency throughout the pool
- B** Unique triple brush system removes algae and bacteria while reducing chemical use
- C** Convenient maintenance with patented filter elements with top access for easy draining and cleaning

### Advanced cleaning technologies

- Intelligent, self-adjusting software ensures optimal coverage of all pools, regardless of size or shape
- Effective brush systems for cleaning the surface
- Reliable collection of dirt and debris
- Dual-level filtration system reliably cleans in any position
- Precise cleaning of the waterline efficiently removes layers of oil that have accumulated there





# water

## Standard equipment of the Salt Water Station

### 1 Electronic unit

- Fire-resistant ABS plastic in compact size with 4.3" touch display
- Integrated alarms for all types of malfunctions
- Self-cleaning cells can be programmed according to water hardness to extend cell service life up to 15,000 hours
- Records operating hours
- Display of cell efficiency
- Notification of the end of the cell life cycle
- Integrated filter pump control (also for speed-controlled pumps)
- Integrated lighting control
- Integrated temperature control

### Hydrolise intensity control

A 16-bit microprocessor controls the production of oxidants and regulates the current intensity. The system produces hypochlorite as well as ozone and oxygen and other disinfectants in water with a minimum conductivity between 500 and 6,000 mS

### 2 Self-cleaning cell

The cell is anionic and cathodic coated. This ensures the production of disinfectants even during the self-cleaning process

### Optional special features:


- Network-compatible through Ethernet module
- pH-value control
- fully automatic free chlorine measurement




## Pool controller

The pool controller makes it easy to control your pool. The Pool-Controlling-System for perfect water care and complete control of circulation pump, heating, spotlights, water attractions and other features. Additional relays can be used to control other functions such as roller blinds, backwash control with bar valve, massage jets, counter-current system, garden lighting, etc.

The clear menu structure makes the operation of the pool controller simple and intuitive. A self-explanatory touch screen simplifies the use of the pool controller considerably. The unit can be accessed remotely via the local network or via the Internet. Thanks to real-time transmission, operation via remote access takes place in the same way as if you were standing in front of the unit yourself.



- 1 Touchscreen
- 2 pH pump
- 3 Floccing pump
- 4 Cell with test tap
- 5 Pool controller



# water treatment





XL-Lounger 95 | Papyrus White | Vita Bad AG



# Pool Controller features

- Elegant **design**
- Easy and intuitive **operation** via touchscreen
- Standard control of circulation pump, heater, spotlight, etc.
- Multiple **connection options** via additional relays of additional devices, such as roller blind control, level control, backwash control with bar valve, massage jets, counter-current system, surge, garden lighting, etc.
- **Free chlorine measurement** for perfect water quality in conjunction with the proven hydrolysis.

- Measures continuously measures the free chlorine level (ppm) and automatically activates the titanium cell of the hydrolysis when the measured value falls below the set value. (Optionally, the pool controller can also be used with chlorine or oxygen).
- **Flocculant dosing pump** with quiet peristaltic pump
- **ph control**  
A precise, automatic measurement and control of the pH value in the water incl. dosing
- **Temperature**  
Setting and control of the water temperature

- in connection with swimming pool heating, such as air heat pump, heat exchanger, etc.
- **Measuring cell** with sampling tap as well as flow monitoring and setting
- **History**  
Wide-ranging long-term logbook function for storing operating data
- **Remote display and operation** via PC, smartphone, tablet, etc. (Internet connection required)





# Pool collection

**PLUNGE POOLS**

- X-Trainer 45**  
4,45 x 2,94 x 1,21-1,49
- Classic 53**  
5,30 x 3,15 x 1,50
- Classic 63**  
6,37 x 3,15 x 1,50
- Classic**  
6,16 x 3,16 x 1,50
- Aqua Nova 53**  
5,30 x 3,20 x 1,50
- Classic Top**  
6,37 x 3,23 x 1,10

---

**SMALL**

- Classic 73**  
7,37 x 3,15 x 1,50
- Brilliant 66**  
6,62 x 3,62 x 1,40
- Brilliant 74**  
7,63 x 3,64 x 1,40
- Riverina 67**  
6,72 x 3,44 x 1,11-1,57
- Trend 73**  
7,30 x 3,30 x 1,50
- Baby-Pool**  
6,52 x 2,40 x 0,88
- XL-Trainer 72**  
7,19 x 3,30 x 1,50
- Fun 74** **Fun 74 S**  
7,48 x 3,68 x 1,50  
7,50 x 3,71 x 1,50

---

**HIGH-END**

- Infinity 80**  
8,30 x 4,05 x 1,46
- Yacht Pool**  
11,54 x 4,04 x 1,50
- XXL-Trainer 133**  
13,28 x 4,49 x 1,50
- CompassSwim 50**  
5,00 x 2,45 x 1,35
- CompassSwim 60**  
6,00 x 2,45 x 1,35

**MEDIUM**

- Classic 83**  
8,37 x 3,52 x 1,50
- Classic 93**  
9,37 x 3,52 x 1,50
- Aqua Nova 77**  
7,75 x 3,55 x 1,50
- Aqua Nova 84**  
8,40 x 3,55 x 1,50
- X-Trainer 82**  
8,25 x 3,68 x 1,09-1,76
- XL-Brilliant 88**  
8,70 x 3,75 x 1,50
- Fun 80** **Fun 80 S** **Fun 80 D**  
8,00 x 3,70 x 1,50

---

**LARGE**

- Classic 103**  
10,37 x 3,52 x 1,50
- Riverina 106**  
10,62 x 3,78 x 1,04-1,88
- Java 101**  
10,03 x 3,80 x 1,50
- XL-Java 114**  
11,40 x 3,96 x 1,10-1,68
- Fun 100**  
10,00 x 4,00 x 1,50
- XL-Lounger 115**  
11,50 x 4,06 x 1,50
- XL-Lounger 95**  
9,52 x 4,06 x 1,50
- XL-Trainer 110 FB**  
11,02 x 4,02 x 1,50
- XL-Fast Lane 122**  
12,15 x 2,89 x 1,50

**R** – Compass Rollo Cover optional





**COMPASS**   
*enjoy the moment*

Subject to misprints, changes and errors.

